



project »« profile }

SEVERSTAL NA LTD.

Dearborn, MI

Project Overview:

Onex Construction installed the refractory linings on two new Zinc Pots at Severstal NA. Each Zinc Pot was constructed using a combination of brick and castable. Precision brick work was required to achieve the reverse arch design on each of the sidewalls. This project was completed in January of 2012.

- Construction of two new Zinc pots – GA and GI type
- Inductotherm Design
- New refractory reinstall
- Each Zinc pot was 62 t
- Onex also fabricated the steel form for the zinc pot throats
- Completed ahead of schedule and on budget in 2012

References:

CHRIS HOFE

Barton Malow – Project Manager

309-697-7527



ONEX
CONSTRUCTION